



P.O. Box 2359, Abingdon, VA 24212

Phone: (276) 628-1600

Fax: (276) 623-1185

## REQUEST FOR QUOTE

### HABITAT RESTORATION PROJECT CHILHOWIE, SMYTH COUNTY, VIRGINIA

**DUE DATE – 9/19/2018**  
**PRE-BID SITE VISIT – TO BE DETERMINED**

The Upper Tennessee River Roundtable (UTRR) is soliciting this Request for Quote for the Chilhowie Town Park on the Middle Fork Holston River (RM 28.0) Habitat Restoration Project in Chilhowie, Smyth County, Virginia. The project will be funded by UTRR, in collaboration with the U.S. Fish and Wildlife Service, Virginia Department of Game and Inland Fisheries, and the landowner. Project construction is anticipated to begin October 2018 and must be completed no later than December 2018.

#### **SCOPE OF WORK**

The Site Contractor shall implement the instream restoration project according to the Construction Plan Sheets (dated 4/17/2018) provided, adhering to all federal, state, and local environmental permits. Construction oversight shall be provided by U.S. Fish and Wildlife Service and UTRR. Any deviation from the Construction Plan Sheets shall be approved by the Project Manager (Corey Kanuckel, U.S. Fish and Wildlife Service, corey\_kanuckel@fws.gov, 804-694-9064).

The Site Contractor SHALL be responsible for the following Services, including Equipment and Labor:

#### *Habitat Restoration Construction*

- Sediment and Erosion Control, including Permanent Seeding, and Silt Fencing as needed.
- Construction Entrances
- Root Wad and Large Woody Debris Acquisition (on-site)
- In-Stream Structure Installation of Boulder Clusters & Slab Rock, Footer Rock, Root Wads, and Large Woody Debris

The Site Contractor SHALL NOT be responsible for the following Services, which will be provided by others:

- Streambank Grading
- Streambank Stabilization (Riparian Permanent Seeding and Streambank Matting)
- Hauling Excavated Streambank Material to Designated Site
- Live stake Installation (Implemented in February-March 2019)
- Riparian Tree/Shrub and Wetland Plantings (Implemented in February-April 2019)

UTRR shall provide the following Materials:

- Silt Fence
- Geotextile Liner (Construction Entrance)
- All Rock Material; including Boulders (Root Wad Footer Rocks and Boulder Clusters), Slab Rock, 2-4" Stone (Construction Entrance), 1-2" Stone (Structure Backfill)
- Streambank Matting and Stakes (Streambank Stabilization)
- Permanent Seed (Erosion Control)
- Temporary Seed (Erosion Control)
- Riparian Permanent Seed Mix (Streambank Stabilization)

The Site Contractor shall provide the following Materials:

- Straw for Permanent Seeding (Estimate 100 Bales)

Additional materials needed shall be approved by the Project Manager before submittal for reimbursement.

### QUOTE FOR SERVICES

Please provide a Quote for the Scope of Work described above, for equipment and labor time, and materials to complete.

1) Mobilization/Demobilization	\$ _____ (Lump Sum)
2) Superintendent & Truck	\$ _____ (Hourly Rate)
2) 314 Excavator with Bucket and Thumb	\$ _____ (Hourly Rate)
3) Dump Truck (Track Truck)	\$ _____ (Hourly Rate)
5) Labor	\$ _____ (Hourly Rate)
5) Straw Bales	\$ _____ (Each)

Please provide a list of past stream or river restoration related projects that your company has participated in (up to 5 projects); a brief summary of project involvement; and a list of any certifications or training that staff have completed in this field. Contracts will be awarded based on consideration of both project cost and project experience.

Please return Quotes to Carol Doss (Executive Director, UTRR, [uppertnriver@yahoo.com](mailto:uppertnriver@yahoo.com), 276-628-1600) by email or fax (276-623-1185). Quotes will be accepted through September 19, 2017. A pre-bid site visit will be scheduled upon request.