



P.O. Box 2359, Abingdon, VA 24212

Phone: (276) 628-1600

Fax: (276) 623-1185

REQUEST FOR QUOTE

SOUTH FORK CLINCH RIVER (DUNFORD PARK) RESTORATION PROJECT TAZEWELL, TAZEWELL COUNTY, VIRGINIA

DUE DATE – 12/8/17
PRE-BID SITE VISIT – TO BE DETERMINED

The Upper Tennessee River Roundtable (UTRR) is soliciting this Request for Quote for the South Fork Clinch River Stream Restoration Project in Dunford Park located in the Town of Tazewell, Tazewell County Virginia. The project is funded through a grant from the Virginia Department of Environmental Quality (DEQ) and awarded to the UTRR (contract #16441). Project activities are in coordination with the UTRR, U.S. Fish and Wildlife Service, Virginia Department of Game and Inland Fisheries, and the Town of Tazewell. Project construction is anticipated to begin January 2018 and must be completed no later than April 15, 2018.

SCOPE OF WORK

The Site Contractor shall implement the stream restoration project according to the Construction Plan Sheets (dated 9/15/2017) provided, adhering to all federal, state, and local environmental permits. Construction oversight shall be provided by U.S. Fish and Wildlife Service and UTRR. Any deviation from the Construction Plan Sheets shall be approved by the Project Manager (Corey Kanuckel, USFWS Partners for Fish & Wildlife Program, corey_kanuckel@fws.gov, 804-694-9064).

The Site Contractor SHALL be responsible for the following Services, including Equipment and Labor:

Stream Restoration Construction

- Sediment and Erosion Control, including Permanent Seeding, and Silt Fencing as needed.
- Construction Entrances
- Streambank and Floodplain Grading
- Installation of Toe Protection, including Coir logs, Rootwads/Large Woody Debris, and Temporary Stream Crossings
- Streambank Stabilization (Streambank Matting)
- Hauling excavated floodplain material to designated site (3 miles from project site, estimated 750 cubic yards)

The Site Contractor SHALL NOT be responsible for the following Services*, which will be provided by UTRR:

- Livestake Installation (Implemented in February-March 2018)
- Riparian Tree/Shrub Plantings (Implemented in February-April 2018)

*unless equipped to provide riparian planting and interested in including quote for services

UTRR shall provide the following Materials to the Site Contractor:

- Silt Fence
- Geotextile Liner (Construction Entrance)
- All Rock Material; including Boulders (Rootwad Footer Rocks), 2-4" Stone (Construction Entrance), 1-2" Stone (Structure Backfill)
- Streambank Matting and Stakes (Streambank Stabilization)
- Permanent Seed (Erosion Control)
- Temporary Seed (Erosion Control)
- Riparian Permanent Seed Mix (Streambank Stabilization)

The Site Contractor shall provide the following Materials:

- Straw for Permanent Seeding

Additional materials needed shall be approved by the Project Manager before submittal for reimbursement.

QUOTE FOR SERVICES

Please provide a Quote for the Scope of Work described above, for equipment and labor time, and materials to complete.

- | | |
|--|---------------------------|
| 1) Stream Restoration Construction | \$ _____ (Lump Sum) |
| 2) Hauling Excavated Floodplain Material | _____ (Hourly Rate) |
| | _____ (Estimated CY/Load) |
| 3) Riparian Planting & Materials* | _____ (Lump Sum) |

*optional quote

Please provide a list of past stream/river restoration related projects that your company has participated in (up to 5 projects); a brief summary of project involvement; and a list of any certifications or training that staff have completed in this field. In addition, please provide a list of 3 references and indicate whether your company has workers comp insurance. Contracts will be awarded based on consideration of both project cost and project experience.

Please return Quotes to Carol Doss (Executive Director, UTRR, uppertnriver@yahoo.com, 276-628-1600) by email or fax (276-623-1185). Quotes will be accepted through December 8, 2017. A pre-bid site visit will be scheduled upon request.